

MEGAN M. GREVE
Director
mmgreve@solanocounty.com
(707) 784-7900

DEPARTMENT OF GENERAL SERVICES
Capital Projects Management Division



SOLANO
COUNTY

MARK A. HUMMEL, AIA
Capital Projects Manager
MAHummel@SolanoCounty.com
(707) 784-7908

675 Texas Street, Suite 2500
Fairfield, CA 94533-6342
(707) 784-7908
Fax (707) 784-7912

DATE: March 23, 2020
TO: All Interest Bidders

SUBJECT: Addendum 02 to Contract Documents for:
**1665 – Department of Child Support Services (DCSS) Relocation Project
located at 675 Texas Street, Fifth Floor, Fairfield, CA 94533**

This ADDENDUM shall be considered part of the bid documents for the above-mentioned projects as though it had been issued at the same time and shall be incorporated integrally therewith. Where provisions of the following supplementary data differ from those of the original bid documents, this ADDENDUM shall govern and take precedence.

Bidders are notified that they shall make **any** necessary adjustment(s) in their estimates on account of this ADDENDUM. It will be construed that each bidders' proposal is submitted with full knowledge of all modifications and supplemental data specified herein.

The clarifications and/or additions and/or deletions that are described in this ADDENDUM shall be included in the Specifications and/or Drawings.

This ADDENDUM supersedes the original DRAWINGS and SPECIFICATIONS dated 12/13/2019; Divisions 00 and 01 dated 02/21/2020; and Addendum #1 dated 03/20/2020, where it contradicts them; all other conditions remain unchanged.

The bid date has been changed; bids are due by 2:00 PM local time, March 31, 2020, at the Solano County General Services Department, Capital Projects Management Division, 675 Texas Street, Suite 2500, Fairfield, California 94533.

Acknowledgment of receipt of this ADDENDUM is required on the Bid Form. The Acknowledgment Form is included in the Specifications of Page 1, Section 00 41 00.

ADDENDUM NO. 2

Addendum No. 2 is being issued to the Contract Bid Documents for the above referenced project.

PART A – LIST OF QUESTIONS AND ANSWERS (none); and **PART B – COUNTY CLARIFICATIONS/REVISIONS TO SPECIFICATIONS/ DRAWINGS**

PART B – COUNTY CLARIFICATIONS/REVISIONS TO SPECIFICATIONS/ DRAWINGS

Clarification 01

Revised Bid Due Date

REPLACED sealed bid due date to March 31, 2020 at 2:00 P.M., local time, under Specification 00 11 00 – Notice to Bidders (Part III) and Specification 00 21 00 – Instructions to Bidders (Section 1.05.B). All other information remains the same.

Clarification 02

Low Voltage – Manufacturer

Any reference to "Leviton (or equal)", replace with Panduit.

Clarification 03

Low Voltage Cabling – Homerun to Data/Phone Room A578

Replace sheet note in drawing T2.10:

“B. ALL CABLING SHALL BE HOMERUN TO DATA/ PHONE ROOM A578. TERMINATE CATEGORY CABLING IN 48 PORT PATCH PANELS, 2U WIRE MANAGERS BETWEEN PATCH PANELS. LABEL ALL CABLING FACEPLATES AND PATCH PANELS PER TIA 606 STANDARDS. NEW CABLES SHOULD BE ADDED TO THE MIDDLE RACK AND MATCH THE CURRENT DESIGN AND NUMBERING SCHEME, ADD NEW PATCH PANELS AND WIRE MANAGEMENT AS NEEDED (PANDUIT). IN THE EVENT CABLES EXCEED THE MIDDLE RACK, COORDINATE WITH SOLANO COUNTY IT DEPARTMENT FOR FURTHER DIRECTION.”

Clarification 04

A/V Basis of Design – Main Lobby and Outside Interview Room 5605A

Under Basis of Design in drawing T2.10 for Main Lobby and Outside Interview Room 5605A, replace reference to “A/V over IP controller” with “HD-based T-extenders”.

(END OF ADDENDUM 2)